ISO New England Inc 2017 Prior Year List of Projects Designated to the PTOs Attachment K, Section 4.1(j)(iii)

Transmission

Owner **Key Study Area** Project ID **Solution Component (Project)** Responsible for

the Provigation 1

ISO New England Inc 2017 Prior Year List of Projects Designated to the PTOs Attachment K, Section 4.1(j)(iii)

Key Study Area	Project ID	Solution Component (Project)	Transmission Owner Responsible for the Project	Need By Date	Actual In- service Date
Southeastern Massachusetts and Rhode Island	1730	Extend the 115 kV 114 line from Eversource/National Grid border to Industrial Park Tap	Eversource	Prior to 2016	TBD
Southeastern Massachusetts and Rhode Island	1731	Install 35.3 MVAr 115kV capacitors at High Hill Substation #644 and Wing Lane Substation #624	Eversource	Prior to 2016	TBD
Southeastern Massachusetts and Rhode Island	1736	Reconductor the 108 line from Bourne Substation #917 to Horse Pond Tap	Eversource	2016	TBD
Southeastern Massachusetts and Rhode Island	1723	Reconductor L14 and M13 from Bell Rock to Bates Tap (8.3 miles each)	National Grid	Prior to 2016	TBD
Southeastern Massachusetts and Rhode Island	1735	Replace wave trap on 114 line at Tremont Substation #713	Eversource	Prior to 2016	TBD
Southeastern Massachusetts and Rhode Island	1732	Loop 201-502 line into Medway #65 Substation to form the 201-502N and 201-502S lines	Eversource	Prior to 2016	TBD
Southeastern Massachusetts and Rhode Island	1737	Replace disconnect switches 107A, 107B, 108A and 108B on Line 323 at West Medway Substation #446	Eversource	2018	TBD
Southeastern Massachusetts and Rhode Island	1728	Build a new Carver to Kingston 115 kV line and Carver terminal	Eversource	2016	TBD

Southeastern Massachusetts and Rhode Island