

ISO New England Inc  
2017 Prior Year List of Projects Designated to the PTOs  
Attachment K, Section 4.1(j)(iii)

| Key Study Area | Project ID | Solution Component (Project) | Transmission<br>Owner<br>Responsible for<br>the Project |
|----------------|------------|------------------------------|---|
|----------------|------------|------------------------------|---|

**ISO New England Inc  
2017 Prior Year List of Projects Designated to the PTOs  
Attachment K, Section 4.1(j)(iii)**

| Key Study Area                              | Project ID | Solution Component (Project)   | Transmission Owner Responsible for the Project | Need By Date  | Actual In-service Date |
|---|------------|--|--|---------------|------------------------|
| Southeastern Massachusetts and Rhode Island | 1730       | Extend the 115 kV 114 line from Eversource/National Grid border to Industrial Park Tap           | Eversource                                     | Prior to 2016 | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1731       | Install 35.3 MVar 115kV capacitors at High Hill Substation #644 and Wing Lane Substation #624    | Eversource                                     | Prior to 2016 | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1736       | Reconductor the 108 line from Bourne Substation #917 to Horse Pond Tap                           | Eversource                                     | 2016          | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1723       | Reconductor L14 and M13 from Bell Rock to Bates Tap (8.3 miles each)                             | National Grid                                  | Prior to 2016 | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1735       | Replace wave trap on 114 line at Tremont Substation #713   | Eversource                                     | Prior to 2016 | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1732       | Loop 201-502 line into Medway #65 Substation to form the 201-502N and 201-502S lines             | Eversource                                     | Prior to 2016 | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1737       | Replace disconnect switches 107A, 107B, 108A and 108B on Line 323 at West Medway Substation #446 | Eversource                                     | 2018          | TBD                    |
| Southeastern Massachusetts and Rhode Island | 1728       | Build a new Carver to Kingston 115 kV line and Carver terminal                                   | Eversource                                     | 2016          | TBD                    |

Southeastern  
Massachusetts  
and Rhode Island

